



ALCALDÍA MUNICIPAL DE COTUÍ
Gerencia de Planeamiento Urbano
Tel.: 829-813-5252, Fax.: 809-240-4991
RNC: 404-00031-6

PRESUPUESTO: ACERAS Y CONTENES SECTOR LOS PINOS

No.				
	Cantidad	Ud.	Precio	Valor
1 PRELIMINARES				
1.1 Letrero en obra	1.00	PA	RD\$ 10,000.00	RD\$ 10,000.00
1.2 tarja	1.00	PA	RD\$ 16,000.00	RD\$ 16,000.00
1.3 Levantamiento Topografico	1.00	PA	RD\$ 25,000.00	RD\$ 25,000.00
1.4 Limpieza con equipos	990.00	M3	RD\$ 20.00	RD\$ 19,800.00
			Sub-Total:	RD\$ 70,800.00
2 MOVIMIENTOS DE TIERRA				
2.1 Bote Material	257.40	M ³	RD\$ 270.00	RD\$ 69,498.00
2.2 Relleno compactado	1,320.00	M ³	RD\$ 705.90	RD\$ 931,788.00
2.3 Terminación de Superficie	6,600.00	M ²	RD\$ 22.09	RD\$ 145,794.00
			Sub-Total:	RD\$ 1,147,080.00
3 CONSTRUCCION DE BADENES				
3.1 Badén 8M x 1.40M x 0.60M (A.T.C)	4.00	UD	RD\$ 33,511.95	RD\$ 134,047.80
			Sub-Total:	RD\$ 134,047.80
4 CONSTRUCCION ACERAS Y CONTENES				
4.1 Construcción de Contenes	1,100.00	ML	RD\$ 615.41	RD\$ 676,951.00
4.2 Construcción de Aceras	1,000.00	M ²	RD\$ 602.52	RD\$ 602,520.00
4.3 Relleno Bajo Acera. e=0.20 mts	200.00	M ²	RD\$ 701.21	RD\$ 140,242.00
			Sub-Total:	RD\$ 1,419,713.00
SUB-TOTAL COSTOS DIRECTOS:				RD\$ 2,771,640.80
5 Costos Indirectos				
5.1 Dirección Técnica	10%	RD\$		277,164.08
5.2 Transporte	3%	RD\$		83,149.22
5.3 Codia	0.10%	RD\$		2,771.64
5.4 Seguros y Fianzas	4.50%	RD\$		124,723.84
5.5 Gasto Administrivos	3%	RD\$		83,149.22
5.6 Fondo de pensiones (Ley 6-86)	1.0%	RD\$		27,716.41
5.8 Imprevistos	5%	RD\$		138,582.04
5.9 ITBIS	18%	RD\$		49,889.53
SUB-TOTAL COSTOS INDIRECTOS:				RD\$ 787,145.99
TOTAL GENERAL:				RD\$ 3,558,786.79